



Schenectady County  
Purchasing Department

620 State St.-2<sup>nd</sup> Floor  
Schenectady, NY 12305  
[purchasing@schenectadycountyny.gov](mailto:purchasing@schenectadycountyny.gov)  
518.388.4240

**ADDENDUM**

---

**RFB-2024-45**  
**RENOVATIONS TO PRINCETOWN SHERIFF'S SUBSTATION**  
**C2 DESIGN GROUP**

**ADDENDUM #2**

Issued Date: 06/10/2024

The purpose of this addendum is to provide detailed information to all Bidders. This addendum is hereby included in and made part of the Contract Documents, whether or not attached thereto. Receipt of this Addendum must be acknowledged on the bid form.

**CONTENTS/RESPONSE TO QUESTIONS/REFERENCE TO ATTACHMENTS**

**General:**

1. This addendum changes the documents for Bid #RFB-2024-45.
2. Drawing A901 – Finish Plan and Schedules
  - a. Finish Schedule
    - i. (Room) 108 – Break Room Revise all Base and trim marked as ETR to PT-2 (Color as selected by Owner.)

**Requests for Information and Response:**

1. As per Drawing P001, Plumbing Fixture Schedule, Stainless Steel Tank Type toilet?
  - a. Response: See Plumbing Fixture Schedule, Manufacture and Model: Stainless-AD #WC-Tank.
2. As per Drawing A600, Detail 2/A600, we have to supply and install Rubber Floor (RF-1) to plywood substrate, but there is not any information related to the basis of design.
  - a. Response: The Rubber Floor at the ramp (RF-1) shall be **Roppe | Recoil | 376 Bisque Ivory | Roll – (5/32" GA).**
3. As per Drawing A-901 & Finish Legend the Basis of Design for the Carpet Tile will be (J+J Flooring Group, Boucle, 2711 KNIT, 12"x48") but the Specification 096800 Carpet Tile call out (Shaw

Contract, collection Diffuse + Disperse and Style Diffuse Ecologyx 4, Size 24"x24"). Could you clarify which one has to be provided?

- a. Response: Provide carpet as listed on Drawing A-901 & Finish Legend.
4. Drawing A100, Keynotes 112 & 121 noted wall mounted handcuffs, but there is not any specification related to them, who is responsible to provide and install them? If this one is part of the GC Scope Work, could you provide Basis of design?
    - a. Response: Wall and floor mounted handcuff restraint use KryptoMax | Stainless Steel Handcuff Ring: Model # KM-WHCR (3/8" Solid Round Rod welded to 12 GA 6"x6" stainless steel plate)
    - b. Secure to solid blocking with tamper resistant hardware per manufacturer specifications.
  5. The Project Manual has a specification for Rubber Wall Base, could you indicate where is this applicable?
    - a. Response: Rubber wall base is not required for the job. All locations to be wood base per the drawings.
  6. I'm reaching out to see if there was a budget for this project.
    - a. Response: There is no project budget.

**Please acknowledge this addendum on your bid form.**

**END OF ADDENDUM #2**